



143 Gunnedah Road  
P O Box 7090 NEMSC  
Tamworth, NSW 2348  
Australia

Ph: (02) 6755 6000  
Fax: (02) 6755 6006  
e: [sales@monitor.net.au](mailto:sales@monitor.net.au)

## MONITOR MACHINE INDUCTION

MODEL :

PLATFORM 1365 & 1380

**Note** : Operators of boom lifts over 11 metres platform height are required to hold an EWP WorkCover licence. For all other lifts, an EWPA Yellow Card is recommended.....

**Warning!** This is a basic induction only, and is not designed to remove the responsibility the operator has to be fully conversant with the Operator's Manual and any site-specific requirements.....

### INTRODUCTION:

- 1) Safety harnesses must be worn .....
- 2) Identify Safe Working Load .....
- 3) Height / weight limit features (if applicable) .....
- 4) Limit switches must not be tampered with .....
- 5) Identify Wind Load Rating on Compliance Plate .....
- 6) Identify swing and crush hazards .....
- 7) Logbook must be filled in daily .....
- 8) Operators manual for technical assistance .....
- 9) Personal protective clothing and / or equipment requirements.....

OPERATION: (Note: Perform pre-operation checks ! ).....

- 1) Drive.....
- 2) Use caution on uneven ground. Use stabiliser legs as a safety precaution.....
- 3) Reverse up slopes.....
- 4) Do not leave parked on a slope (no handbrake).....
- 5) Always drive with tracks expanded unless access is limited .....
- 6) Keep well clear of the machine when driving .....
- 7) Either stand in the basket, or stay at least 1 mt away from the machine.....
- 8) Never stand on the lower side of the machine on a slope.....

### Stabilizer Legs:

- 9) Operate two legs together, smoothly and carefully.....
- 10) Level machine using level indicator.....
- 11) Use extreme caution on sloping terrain .....

- 12) Check stability of ground under stabilizers.  
Avoid soft or unstable ground. Be aware of any underground hazards.....
- 13) Do not operate without all 4 legs properly deployed.....

Boom operation:

- 14) Levers and their functions .....
- 15) Duplicate controls at ground for emergency use .....
- 16) Emergency lowering system .....
- 17) Emergency operation of stabilisers and drive.....
- 18) Operation of "Emergency Rescue" (if fitted) for retrieval of overloaded basket.....
- 19) Critical importance of re-sealing emergency valves (if opened) before operating again. ....
- 20) Dangers of overhead power: non-insulated booms .....
- 21) Do not use as crane or tie items to platform.....
- 22) Boom must be completely down before using other functions .....
- 23) Removal of basket – ensure security pin is in place after refitting.....

Dual power: DO NOT operate on the combustion engine in poorly ventilated areas .....

- 24) Change from Honda Petrol to 240v or battery drive .....
- 25) 240 volt outlet in platform .....
- 26) Earth leakage relay.....

27) High pressure outlet: fitting at ground and platform.....

TRAILER:

- 1) Loading and unloading .....
- 2) Correct load balance .....
- 3) S.W.L. of towing vehicle .....
- 4) Brakes and adjustments .....
- 5) Safety chain connection .....
- 6) Correct tie-down method .....
- 7) Setting up on trailer is not allowed.....
- 8) Handbrake on in towing vehicle + remove keys and lock doors to prevent unauthorised access .....

SERVICE:

- 1) Any faults or requirements must be immediately discussed w/- Monitor before further operation.....
- 2) Flashing lights and movement alarms must not be disconnected.  
Report any malfunction immediately .....
- 3) Monitor must service the machine every 100 hours or 3 months by regulation.  
Advise Monitor if the machine reaches either of these intervals. The machine

can be serviced on site without any inconvenience to the hirer.....

OTHER:

- 1) Hirer's responsibilities (theft / damage) .....
- 2) Theft & Damage Waiver: reduces liability.....
- 3) Hire Contract Terms & Conditions.....
- 4) Monitor contact numbers for any assistance .....
- 5) Notes:

---

---

---

---

---

---

---

Date: \_\_\_ / \_\_\_ / \_\_\_

Location: \_\_\_\_\_

I acknowledge I have completed the above induction and fully understand each point covered.

Signature: \_\_\_\_\_

Name: \_\_\_\_\_

Ph: \_\_\_\_\_

Employer: \_\_\_\_\_

Ph: \_\_\_\_\_

Address: \_\_\_\_\_

Fax: \_\_\_\_\_

The above induction was given and completed by:

\_\_\_\_\_

Print Name

\_\_\_\_\_

Signature